

ROTA BOY® - PANEL LIFTING AND TURNING MACHINE

The Rota Boy® is a specialist vacuum panel lifting machine with the unique ability to rotate panels through 180° avoiding the need for manual handling and panel turning.

The Rota Boy® is designed to handle Kingspan KS1000RW and KINGZIP® roof panels or equivalent in lengths from 10m to 20m and roof pitches up to 25°. Suspended from a crane, the machine will lift panels directly from the delivery packs, rotate where necessary and lift them safely onto the roof structure.

The lifter works from internal batteries and when fully charged it will provide a full days operation, allowing high productivity to be achieved.

The Rota Boy® hire rates are as follows –

Initial Delivery to site	£100.00
Site training – compulsory for first time users	£100.00
First week hire – minimum charge	£450.00
Second & subsequent weeks – charged daily	£450.00/week
Collection on completion	£100.00

These rates will apply unless otherwise agreed in writing between both parties.

